



सीएसआईआर - भारतीय रासायनिक प्रौद्योगिकी संस्थान  
**CSIR - Indian Institute of Chemical Technology**  
 (Council of Scientific and Industrial Research)

विज्ञान एवं प्रौद्योगिकी मंत्रालय, भारत सरकार / Ministry of Science & Technology, Govt. of India.  
 तारनाका, हैदराबाद, तेलंगाना / Tarnaka, Hyderabad, Telangana - 500 007

**NOTICE INVITING TENDERS**

REF NO: CSIR-IICT/ZM-SCHOOL/2026-27

DATE: 11.06.2026

The Director CSIR-IICT, Tarnaka, Hyderabad invited sealed tenders by **17.06.2026 AT 17.00HRS** from reputed contractors/agencies with established experience and financial solvency to carry out the work - **Providing shed at primary building class room at IICT ZM School, CSIR-IICT, Hyd.**

S.No	Description Of item of work	Qty	Unit	Rate (Rs.)	Amount (Rs.)
1	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	3800.00	Kg		
2	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-Charge) of total coated thickness 0.50mm (base metal of minimum 0.45mm thickness with total coating thickness of 0.05mm) with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	268.00	Sqm		
3	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	5.00	Cum		

*[Signature]*

4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	1.00	Cum		
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:1½:3 (1 Cement: 1½ coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	4.50	Cum		
7	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	268.00	Sqm		
				<b>TOTAL</b>	
				<b>GST if any</b>	
				<b>TOTAL AMOUNT</b>	

**Terms & conditions**

1. The sealed cover should be superscripted "Providing shed at primary building class room at IICT ZM School, CSIR-IICT, Hyd." with last date.
2. Water & Electricity will be provided by CSIR-IICT, Hyderabad to the contractor.
3. The offer /quotation should be addressed to "The Director, CSIR-IICT, Hyderabad".
4. The contractors are advised to visit the site before submit the quotation to have an idea of the execution of the work, failure to do so will not absolve their responsibility to do the work as specified
5. List of documents to be submitted:
  - a) Quotation should be submitted in Contractor's Letter Head with Signature in each page.
  - b) Certificate of Registration for Goods and Service Tax(GST)
  - c) Enlistment order of the contractors of CPWD/PWD or any other Govt Organization in an appropriate class of composite/building category.
  - d) Copy of PAN Card.
6. Percentage of tax (GST) and amount should be mentioned separately in the quotation.
7. Discount offered, if any, may be indicated as a percentage of the order value only.
8. If a tenderer whose tender is accepted fails to undertake the work as per terms of the contract within 10 days to be reckoned from the date of issue of work order.
9. The time allowed for the completion of said work is 30 days from the date of issue of work order.
10. The TDS will be recovered as per rules.
11. The labour engaged and working equipment brought by the contractor for the work shall be recorded in the CSIR-IICT Security Gate before entering into the premises and obtain necessary gate pass.
12. Payment will be made against the bill along with a statement of measurement taken in the presence of the contractor and the Civil Engineer of CSIR-IICT, Hyderabad.
13. The contractor/bidder should indicate their Registration Number, PAN, GST, Bank Account number for making payments to the contractor as well as statutory authorities.
14. Quotation by email or fax will not be accepted.
15. The CSIR-IICT, Hyderabad is not responsible for any damage caused to the labour/manpower engaged by the contractor for execution of the work.
16. Bills submitted by the contractor will be settled after certification by the civil Engineer of IICT with regard to its quality. Any defect in the work has to be rectified free of cost by the contractor within six months from the date of completion of the work.
17. Director, CSIR-IICT, Hyderabad has the right accept any quotation(s) without assigning any reasons.
18. Director, CSIR-IICT, Hyderabad reserves the right to increase/ decrease the quantity of work.

